

**PURNA SAHAKARI SAKHAR KARKHANA LTD; BASMATHNAGAR
DIST.HINGOLI.**

TENDER FORM

प्रति,
मा.कार्यकारी संचालक साहेब
पुर्णा सह.सा.का.लि.,
वसमतनगर.

विषय :- **सी.बी.जी.बायोडायजेस्टर टँक क्र.२ फाउंडेशनच्या कामा बाबत.**

महोदय,
वरील विषयी सविनय सादर करण्यात येते की, मी आपली ई-निविदा सुचना क्र.३२४७ दिनांक १६/०३/२०२६ नुसार खालील अटी व शर्तीप्रमाणे मजुरीदराने काम करण्यास तयार आहे. तरी मला सदरील टँकचे काम करण्याची संधी द्यावी ही विनंती. त्या करीता मी खालीलप्रमाणे मजुरी दर नमुद करीत आहे. तसेच ई-निविदातील व सोबतच्या अटी/शर्ती मला मान्य आहेत.

Item No.	Particulars	Estimated Qty.	Unit	Labour Rate
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m.) By Machine Means.(21.02)	257.37	Cum	Rs.-----
2	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 meters byond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, raming, watering including shoring and strutting etc. Complete (Left upto 1.50 m) By mechanical means (21.06)	257.37	Cum	Rs.-----
3	Excavation for foundation in hard murum and boulders including removing the excavated material uptoadistance 50 metres, beyond the building are a and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and struttingetc. complete. (Lift upto 1.5m.) By Mechanical Means(21.10)	214.48	Cum	Rs.-----
4	Excavation for foundation in Soft rock and old cement or lime masonry foundations including removing the excavated material upto a distance of 50 metres beyond the building are a and stacking as directed, including dewatering, preparing the bed for the foundation and necessary back filling with available earth/murum, ramming,watering including shoring and strutting etc. complete (lift upto 1.5m) By Mechanical Means (21.14)	128.68	Cum	Rs.-----

5	Disposing excavated marterial upto 1 km.	686.32	Cum	Rs.-----
6	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/granite/ quartzite/gneiss for foundation and bedding including bailing out water, steel centering, form work, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete with fully automatic micro processor based PLC with SCADA enabled reversible Drum type mixer/concrete Batch mix plant (Pan mixer) etc. Complete. With fine aggregate (Crushed sand VSI Grade) (24.01)	50.22	Cum	Rs.-----
7	Lean Concrate M-7.5 – 1:4:8	255.67	Cum	Rs.-----
8	Filling in plinth and floors with approved excavated material in 15 cm. To 20 cm. Layers including watering and compacting etc. Complete. (21.36)	961.10	Cum	Rs.-----
9	Providing soling using 80 mm. size trap metal in 15 cm. Layer including filling voids with crushed sand/grit, ramming, watering etc. Complete (21.40)	250.66	Cum	Rs.-----
10	Providing and fixing in position TMT-FE-500 bar reinforcement of varius diameters for R.C.C. pile caps, footing, foundations, slabs, beams columns, canopies staircase, newels, chajjas, lintel pardis, coping, fins, arches etc. As per detailed ddesigns, drawings and schedules, including cutting, bending, hooking the bars, binding with wires or back welding and supporting as required complete. (26.33)	15.9	MT	Rs.-----
11	Providing and laying cast in situ/ready mix cement concrete in M-25 of trap/granite/quartzite/gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover block laying/ pumping, compaction and roughening the surface if special finish is to be provided and curing etc. Complete (Excluding reinforcement nd structural steel) with fully automatic micro processor based PLC with SCADA enabled reversible Drum type mixer/ concrete batch mix plant (Pan mixer) etc. Complete with fine aggregate (Crushed sand VSI Grade) (25.52)	75.18	Cum	Rs.-----

12	Providing and laying cast in situ/ready mix cement concrete M-25 of trap/granite/ quartzire/gneiss metel for R.C.C. slabs and landing as sper detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface aor roughening if special finish is to be provided and curing etc. Complete (Excluding reinforcement and structural steel) with fully automatic micro processor based PLC with SCADA enabled reversible drum type mixer/concrete batch mix plant (Pan mixer) etc. Complete with fine aggregate (Crushed and VSI Grade) (25.72)	123.81	Cum	Rs.-----
13	50 mm. thk. Bitumen with sand layer (Non DSR Item)	834.79	Sqm.	Rs.-----

अटी व शर्ती :-

- १) एक किंवा सर्व निविदा कुठलेही कारण न देता रद्द करणेचा अधिकार कारखान्याने राखून ठेवला आहे.
- २) काम करतेवेळेस आपल्या मजूरास अपघात झाल्यास त्यांची जबाबदारी ठेकेदारावर राहिल.
- ३) कामासाठी लागणारे सर्व मटेरीयल जसे रेडीमिक्स Concrete स्टील, बायडींग वायर, तारखिळे कारखाना पुरवेल, कारखाना स्टोअरमधून मटेरीयल आपणास घेऊन जावे लागेल. कामासाठी लागणारे प्लायवूड, लोखंडी सेन्ट्रींग ठेकेदाराची राहिल.
- ४) सिव्हील विभागाचे व वास्तु सल्लागार यांचे अधिपत्याखाली त्यांचे ड्राईंग व सुचने प्रमाणे काम करावे लागेल.
- ५) वेळेत काम पुर्ण करणे बंधनकारक राहिल.
- ६) कामाचा दर ठरल्यानंतर कुठलीही दरवाढ देण्यात येणार नाही.
- ७) अधिक माहितीसाठी बांधकाम विभागाशी संपर्क साधावा.
- ८) काम समाधानकारक पुर्ण झाल्यानंतर मोजमापानुसार बील देण्यात जाईल.
- ९) प्रत्येक रनिंग बिलातुन ५% सुरक्षा अनामत कपात करण्यात येईल.
- १०) कॉक्रीटींग केलेल्या सर्व कामावर कारखाना तर्फे क्युरींग करण्यात येईल.
- ११) ठेकेदाराने रु.१००/- च्या मुद्रांकावर करारनामा करुन कारखान्यास द्यावा लागेल.

आपलाविश्वासू,

नाव :- -----

पत्ता :- -----

मो.क्र.:- -----